

Metal lockers rough-in inspection checklist

Metal lockers rough-in is the last time the work is fully visible. Once the cover inspection passes and the walls, ceilings and slabs close, every defect left behind becomes a demolition bill. This checklist walks the rough-in in the order the work goes in, with the photo each item needs before it gets buried. Work is commonly verified against manufacturer's published instructions. Confirm the edition your authority having jurisdiction has adopted.

Who runs it: The carpentry crew installing backing, or the GC's superintendent walking the room before the finishes cover the wall.
When: While the walls are open, before drywall and flooring go in and before the locker installer arrives to set units.

Wall backing

- ☐ Continuous backing behind the locker run at anchor height
Solid blocking behind the tops of the lockers at the manufacturer's wall-anchor height, continuous along the run, fastened to studs before the wall closes. 2 photos required

Floor and bench anchorage

- ☐ Bench and locker floor anchors coordinated
Anchor locations for benches and locker bases coordinated with the framing and flooring so anchors land in solid substrate at the right layout. 1 photo required

Layout and clearances

- ☐ Locker run layout fits the room and clearances
Run length, door swing and aisle clearances checked against the room so the lockers land on layout without a filler forced into the corner. 1 photo required